







28 lm

12x lm

**GENERAL SECURITY SPECIFICATIONS:**

1. ALL SECURITY WORK SHALL BE DONE IN ACCORDANCE WITH 2012 IBC, 2014 NEC, 2014 IECC AND ALL OTHER CODES ADOPTED OR AMENDED BY THE GOVERNING BUILDING AUTHORITY AND NECESSARY FOR THE PROPER EXECUTIONS OF THE PROJECT AND A COMPLETED STRUCTURE
2. PROVIDE ALL LABOR, MATERIALS, AND EQUIPMENT NECESSARY FOR THE COMPLETE INSTALLATION AND PROPER FUNCTION OF THE SECURITY SYSTEMS INDICATED ON ALL ELECTRICAL SHEETS.
3. OBTAIN ALL PERMITS, FEES, LICENSES, INSPECTIONS, AND CERTIFICATES OF COMPLIANCE OR APPROVAL AS REQUIRED BY THE GOVERNING BUILDING AUTHORITY.
4. COORDINATE ALL WORK WITH OTHER TRADES AND EXISTING CONDITIONS AS NECESSARY TO INSTALL ALL NEW SECURITY EQUIPMENT WITHIN THE CONFINES OF THE SPACES AVAILABLE AND WITHOUT INTERFERENCES.
5. PLANS ARE INTENDED TO INDICATE THE GENERAL SCOPE OF WORK. DETAILS OF INSTALLATION COVERED BY CODE AND OTHER MINOR ITEMS NOT SHOWN SHALL BE INSTALLED IN ACCORDANCE WITH LOCAL CODES AND ACCEPTABLE INDUSTRY STANDARDS. ALL SECURITY EQUIPMENT AND MATERIALS SHALL BE INSTALLED IN ACCORDANCE WITH LOCAL CODES AND MANUFACTURER'S INSTRUCTIONS. CONTRACTOR SHALL SITE VERIFY EXISTING CONDITIONS AND ALERT ENGINEER OF ANY DISCREPANCIES BEFORE INITIATING WORK.
6. DURING CONSTRUCTION, ALL FIXTURES, EQUIPMENT, PIPES, DUCTS, ETC. SHALL BE COVERED, PLUGGED, OR CAPPED AS REQUIRED TO KEEP CLEAN AND UNDamAGED. ALL DAMAGED ITEMS SHALL BE RESTORED TO ORIGINAL CONDITION OR REPLACED. ALL PROTECTIVE COVERINGS SHALL BE REMOVED BEFORE FINAL ACCEPTANCE.
7. IF CUTTING AND PATCHING OF WALLS, FLOORS, CEILINGS, AND ROOFS IS NEEDED TO INSTALL SECURITY EQUIPMENT. PATCHING WORK SHALL INCLUDE METHODS AND MATERIALS NEEDED FOR AFFECTED SURFACES TO MATCH ADJACENT AREAS. SEAL AROUND ALL EXTERIOR WALL PENETRATIONS WEATHER-TIGHT.
8. WHEN SECURITY EQUIPMENT PENETRATES A ROOF, COORDINATE ALL ROOFING WORK WITH ARCHITECT AND OWNER.
9. FIELD SUPPORT ALL SECURITY SYSTEM EQUIPMENT PER NEC 2014
10. CONTRACTOR SHALL GUARANTEE ALL WORK AND MATERIALS AGAINST DEFECTS FOR A PERIOD OF ONE YEAR FROM FINAL ACCEPTANCE.
11. IN WET LOCATIONS, PROVIDE SEALED, WEATHERPROOF EQUIPMENT.
12. ALL ELECTRICALLY POWERED SECURITY EQUIPMENT TO BE GROUNDED PER NEC 2014.
13. COORDINATE AND PROVIDE ALL WORK INDICATED BY THE DRAWINGS. THIS CONSISTS OF FURNISHING ALL LABOR, EQUIPMENT SUPPLIES AND MATERIALS IN ADDITION TO PERFORMING ALL OPERATIONS INCLUDING CUTTING, CHANNELING AND UNDERGROUND TRENCHING NECESSARY FOR THE INSTALLATION OF COMPLETE SECURITY SYSTEMS AS SHOWN.
14. SECURITY INSTALLATION SHALL INCLUDE A COORDINATION AND CALIBRATION PERIOD THAT INCLUDES DETAILED EFFORTS TO ADJUST THE EQUIPMENT CONFIGURATION TO BEST MEET AND OPTIMIZE ITS EFFECTIVENESS AS DETERMINED BY THE ARCHITECT AND OWNER.

SECURITY SYMBOLS

-  A CEILING CAMERA LOCATION
-  B POLE MOUNTED CAMERA LOCATION
-  C BREAK GLASS SENSOR
-  D DRY CONTACT INPUT SENSOR
-  E ELECTRIC STRIKE
-  F PROXIMITY CARD READER



**AE LEUKEN, LLC**  
ARCHITECTURAL ENGINEERS

1122 N. EL PASO ST  
COLORADO SPRINGS CO, 80903  
PHONE : (719) 398 1155

**MILE HIGH ROSE LLC**  
180 COUNTY RD 599  
WALSENBURG, CO 81089

NO.	DATE	DESCRIPTION

DATE: XX/XX/XXXX  
 CHECKED BY: JJG  
 PROJECT NO: PROJECT#  
 SHEET: SECURITY NOTES

