


philips11:44:30 AM c:\projectwise\pwz_working\dl328826\20755DES_SAO01.dgn

INDEX			CONTRACT ITEM NO.	CONTRACT ITEM	UNIT	ROADWAY			K-18-EP			K-18-EU			K-18-EV			Minor 045A-007100BL		PROJECT TOTALS	
BOOK	PAGE	SHEET				PLAN	AS CONST.		PLAN	AS CONST.		PLAN	AS CONST.		PLAN	AS CONST.		PLAN	AS CONST.	PLAN	AS CONST.
			202-00090	Removal of Delineator	EACH	114														114	
			202-00195	Removal of Median Cover	SY	1,024														1,024	
			202-00200	Removal of Sidewalk	SY	19														19	
			202-00203	Removal of Curb and Gutter	LF	1,239														1,239	
			202-00240	Removal of Asphalt Mat (Planing)	SY	187,614														187,614	
			202-00241	Removal of Asphalt Mat (Planing)(Special)	CY					2,532				791						4,139	
			202-00504	Removal of Expansion Device	LF					59										59	
			202-00810	Removal of Ground Sign	EACH	6														6	
			202-01130	Removal of Guardrail Type 3	LF	5,250														5,250	
			202-01180	Removal of Median Barrier	LF	915														915	
			202-01300	Removal of End Anchorage	EACH	8														8	
			203-00010	Unclassified Excavation (Complete In Place)	CY	19,740														19,740	
			203-00060	Embankment Material (Complete In Place)	CY	5,722														5,722	
			203-01500	Blading	HOUR	160														160	
			203-01510	Backhoe	HOUR	160														160	
			203-01550	Dozing	HOUR	160														160	
			203-01594	Combination Loader	HOUR	160														160	
			203-01597	Potholing	HOUR	30														30	
			203-02330	Laborer	HOUR	80														80	
			206-00065	Structure Backfill (Flow-Fill)	CY													15		15	
			207-00205	Topsoil	CY	8,070														8,070	
			208-00002	Erosion Log Type 1 (12 Inch)	LF	5,000														5,000	
			208-00020	Silt Fence	LF	5,000														5,000	
			208-00035	Aggregate Bag	LF	150														150	
			208-00041	Rock Check Dam	EACH	10														10	
			208-00045	Concrete Washout Structure	EACH	4														4	
			208-00070	Vehicle Tracking Pad	EACH	4														4	
			208-00103	Removal and Disposal of Sediment (Labor)	HOUR	80														80	
			208-00105	Removal and Disposal of Sediment (Equipment)	HOUR	80														80	
			208-00106	Sweeping (Sediment Removal)	HOUR	80														80	
			208-00107	Removal of Trash	HOUR	80														80	
			208-00207	Erosion Control Management	DAY	218														218	
			210-00473	Reset TV Cameras	EACH	4														4	

Print Date: 3/7/2017	
File Name: 20755DES_SAO01.dgn	
Horiz. Scale: 1:200	Vert. Scale: As Noted
Unit Information	Unit Leader DTD

Sheet Revisions		
Date:	Comments	Init.
<input type="checkbox"/>		
<input type="checkbox"/>		
<input type="checkbox"/>		
<input type="checkbox"/>		

Colorado Department of Transportation



902 Erie Avenue
Pueblo, CO 81001
Phone: 719-562-5509 FAX: 719-546-5702

Region 2 DTD

As Constructed
No Revisions:
Revised:
Void:

SUMMARY OF APPROXIMATE QUANTITIES			
Designer:	LEP	Structure Numbers	
Detailer:	LEP		
Sheet Subset:	SOAQ	Subset Sheets:	01 of 05

Project No./Code	
STM SH45-001	
20755	
Sheet Number	14