

phillips 9:42:48 AM c:\projectwise\pwz_working\at328826\20755DES_SA004.dgn

INDEX			CONTRACT ITEM NO.	CONTRACT ITEM	UNIT	ROADWAY		K-18-EP				K-18-EU				K-18-EV				Minor 045A-007100BL		PROJECT TOTALS	
BOOK	PAGE	SHEET				PLAN	AS CONST.	PLAN	AS CONST.	PLAN	AS CONST.	PLAN	AS CONST.	PLAN	AS CONST.	PLAN	AS CONST.	PLAN	AS CONST.	PLAN	AS CONST.		
			614-81175	Traffic Signal-Light Pole Steel (1-75 Foot Mast Arm)	EACH	2																2	
			614-84100	Traffic Signal Pedestal Pole Aluminum	EACH	3																3	
			620-00002	Field Office (Class 2)	EACH	1																1	
			620-00012	Field Laboratory (Class 2)	EACH	1																1	
			620-00020	Sanitary Facility	EACH	2																2	
			625-00000	Construction Surveying	L S	1																1	
			626-00000	Mobilization	L S	1																1	
			626-01103	Public Information Services (Tier III)	L S	1																1	
			627-00009	Modified Epoxy Pavement Marking(Inlaid)	GAL	488																488	
			627-00011	Pavement Marking Paint (Waterborne)	GAL	1,464																1,464	
			627-30405	Preformed Thermoplastic Pavement Marking (Word-Symbol)	SF	1,406																1,406	
			627-30410	Preformed Thermoplastic Pavement Marking (Xwalk-Stop Line)	SF	27,425																27,425	
			630-00000	Flagging	HOUR	1,600																1,600	
			630-00007	Traffic Control Inspection	DAY	140																140	
			630-00012	Traffic Control Management	DAY	80																80	
			630-80002	Flashing Beacon (Solar)	EACH	40																40	
			630-80338	Barricade (Type 3 M-D) (Temporary)	EACH	40																40	
			630-80341	Construction Traffic Sign (Panel Size A)	EACH	108																108	
			630-80342	Construction Traffic Sign (Panel Size B)	EACH	162																162	
			630-80343	Construction Traffic Sign (Panel Size C)	EACH	8																8	
			630-80344	Construction Traffic Sign (Special)	SF	300																300	
			630-80355	Portable Message Sign Panel	EACH	2																2	
			630-80358	Advance Warning Flashing or Sequencing Arrow Panel (C Type)	EACH	4																4	
			630-80360	Drum Channelizing Device	EACH	200																200	
			630-80363	Drum Channelizing Device (With Light) (Flashing)	EACH	30																30	
			630-80370	Concrete Barrier (Temporary)	LF	2,000																2,000	
			630-80380	Traffic Cone	EACH	200																200	
			630-80384	Tubular Marker	EACH	250																250	
			630-80391	Channelizing Device (Fixed)	EACH	100																100	
			630-85010	Impact Attenuator (Temporary)	EACH	4																4	

Print Date: 3/9/2017
 File Name: 20755DES_SA004.dgn
 Horiz. Scale: 1:200 Vert. Scale: As Noted
 Unit Information Unit Leader DTD

Sheet Revisions		
Date:	Comments	Init.

Colorado Department of Transportation
 902 Erie Avenue
 Pueblo, CO 81001
 Phone: 719-562-5509 FAX: 719-546-5702
 Region 2 DTD

As Constructed	SUMMARY OF APPROXIMATE QUANTITIES			Project No./Code
No Revisions:				STM SH45-001
Revised:	Designer: LEP	Structure Numbers		20755
Void:	Detailer: LEP	Sheet Subset: SOAQ	Subset Sheets: 04 of 05	Sheet Number 17