


Tabulation of Removals									
Station		Side	Removal of Median Cover	Removal of Sidewalk	Removal of Curb and Gutter	Removal of Guardrail Type 3	Removal of Median Barrier	Removal of End Anchorage	Notes
From	To		SY	SY	LF	LF	LF	EACH	
39+24.45	56+93.42	LT				1732		1	
39+15.54	40+03.57	RT				51		1	
79+95.82	82+36.01						240		Median Rail
82+36.01	84+59.81					225			Median Rail
82+36.01	84+78.73					243			Median Rail
82+36.01	84+29.94	RT				156		1	
84+63.70	85+13.74	LT				51		1	
86+46.08	88+35.58					189			Median Rail
86+57.99	88+35.58					179			Median Rail
86+66.79	97+10.04	LT				1009		1	
119+13.48	123+10.27	RT				376		1	
122+52.22	128+14.33	LT				525		1	
124+05.68	130+81.05						675		Median Double rail
163+11.00	168+62.04	LT				514		1	
191+00.00	197+00.00								
ADA Ramps at 11th Street			270	19	24				
0+10.61	1+10.00		109		583				24th Street
0+09.84	1+69.89				64				31st Street
0+10.48	1+65.00		375		568				Spaulding Ave
<b>Project Totals</b>			<b>754</b>	<b>19</b>	<b>1339</b>	<b>5250</b>	<b>915</b>	<b>8</b>	

Print Date: 2/22/2017  
 File Name: 20755DES\_TabRem01.dgn  
 Horiz. Scale: 1:1      Vert. Scale: As Noted  
 Unit Information      Unit Leader DTD

Sheet Revisions		
Date:	Comments	Init.

Colorado Department of Transportation  
 902 Erie Avenue  
 Pueblo, CO 81001  
 Phone: 719-562-5509      FAX: 719-546-5702  
 Region 2      DTD

As Constructed  
 No Revisions:  
 Revised:  
 Void:

TABULATION OF REMOVALS  
 Designer: LEP  
 Detailer: LEP  
 Sheet Subset: TAB  
 Structure Numbers  
 Subset Sheets: 05 of 07

Project No./Code  
 STM SH45-001  
 20755  
 Sheet Number 24