

philipsi 9:53:35 AM c:\projectwise\pwrz_working\dl328826\20755DES_TabGuard01.dgn

Tabulation of Guardrail										
Station		Side	Guardrail Type 3 (6-3 Post Spacing)	Guardrail Type 3 (Double) (6-3 Post Spacing)	Guardrail Type 7 (Style CC)	Transition Type 3G	Transition Type 3H	Median Terminal	End Anchorage (Flared)	Remarks
From	To		LF	LF	LF	EACH	EACH	EACH	EACH	
39+43.14	43+05.44	LT	362.5			1			1	
39+32.81	39+51.55	RT	12.5				1		1	
79+70.62	84+41.06			475		1		1		Median
80+26.86	84+26.84	RT	400.0			1			1	
84+47.48	84+59.98	RT	12.5				1			Southbound after K-18-EV
84+82.00	84+94.50	LT	12.5				1			Southbound after K-18-EV
86+85.54	91+66.53	LT	450.0			1			1	
86+34.64	86+47.14	RT	12.5				1			Northbound after K-18-EU
86+64.75	86+77.25	LT	12.5				1			Northbound after K-18-EU
86+76.68	88+76.74	RT		200		1		1		Median
86+85.54	91+35.43	LT	450.0			1			1	
118+45.45	122+45.45	RT	400.0			1			1	
122+52.53	128+02.53	LT	550.0						1	
124+05.85	130+81.05			650				2		Median
164+06.21	168+06.21	LT	400.0						1	
00+10.61	01+10.00				90					24th Street
Project Totals			3075	1325	90	7	5	4	8	

Note:
Guardrail shall have metal posts with synthetic blocks and shall comply with the 31" Midwest Guardrail system as shown in the M&S Standards.

Print Date: 2/22/2017	<input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/>	Sheet Revisions			Colorado Department of Transportation  902 Erie Avenue Pueblo, CO 81001 Phone: 719-562-5509 FAX: 719-546-5702 Region 2 DTD	As Constructed	TABULATION OF GUARDRAIL			Project No./Code
File Name: 20755DES_TabGuard01.dgn		Date:	Comments	Init.		No Revisions:				STM SH45-001
Horiz. Scale: 1:1 Vert. Scale: As Noted						Revised:	Designer: LEP	Structure Numbers		20755
Unit Information Unit Leader DTD						Void:	Detailer: LEP	Subset Sheets:	06 of 07	Sheet Number 25