

**Colorado Department Of Transportation  
Notice To Contractors**

Printed On: **03/27/2017**

Read Order No. 002	Contract ID: <b>C20755</b>	Projects: STMSH45-001
Letting Date: April 20, 2017 10:00 AM	Contract UDBE Goal: 7.00 %	
Region: 2	Guaranty: 5% of Total Bid	
Counties: PUEBLO	For plan pricing, call (303) 757-9313	
	Work Days: 144	
	Res. 2250 DANIEL DAHLKE	(719)562-5509

**Contract Description:**

Project is located on SH 45 (Pueblo Blvd) between mile posts 4.9 and 8.7. Work to included removal of asphalt mat, concrete paving, asphalt paving, grade corrections, shouldering work, signal work, traffic control, and other items as shown in the plans and specs.

Plans, specifications and proposal form may be procured from the Colorado Department of Transportation after 8:00 am, Thursday 3/30/2017

One Publication: 3/30/2017

It is estimated that the total cost of all items in the bid will be:

- Between \$0 and \$1,000,000
- Between \$1,000,000 and \$5,000,000
- Between \$5,000,000 and \$20,000,000
- Greater than \$20,000,000

Item No.	Description	Quantity	Units
	Major Items		
202-00240	Removal of Asphalt Mat (Planing)	187,614.000	SY
202-01130	Removal of Guardrail Type 3	5,250.000	LF
202-01180	Removal of Median Barrier	915.000	LF
203-00010	Unclassified Excavation (Complete In Place)	19,740.000	CY
203-00060	Embankment Material (Complete In Place)	5,722.000	CY
203-01500	Blading	160.000	HOUR
203-01510	Backhoe	160.000	HOUR
203-01550	Dozing	160.000	HOUR
203-01594	Combination Loader	160.000	HOUR
207-00205	Topsoil	8,070.000	CY
208-00002	Erosion Log Type 1 (12 Inch)	5,000.000	LF
208-00207	Erosion Control Management	218.000	DAY
212-00006	Seeding (Native)	15.000	ACRE
212-00032	Soil Conditioning	15.000	ACRE
304-06008	Aggregate Base Course (Class 6) (Special)	13,540.000	CY

Item No.	Description	Quantity	Units
	Major Items		
310-00608	Full Depth Reclamation of Hot Mix Asphalt Pavement (0-8")	168,437.000	SY
403-00720	Hot Mix Asphalt (Patching) (Asphalt)	472.000	TON
403-33871	Hot Mix Asphalt (Grading S) (100) (PG 76-28)	2,872.000	TON
403-34841	Hot Mix Asphalt (Grading SX) (100) (PG 64-22)	450.000	TON
411-10255	Emulsified Asphalt (Slow-Setting)	1,899.000	GAL
412-00825	Concrete Pavement (8-1/4 Inch)	127,640.000	SY
412-00835	Concrete Pavement (8-1/4 Inch) (Fast Track)	32,865.000	SY
412-02000	Concrete Safety Edge	52,300.000	LF
503-00018	Drilled Caisson (18 Inch)	18.000	LF
503-00036	Drilled Caisson (36 Inch)	38.000	LF
503-00048	Drilled Caisson (48 Inch)	42.000	LF
503-00054	Drilled Caisson (54 Inch)	63.000	LF
509-00001	Structural Steel (Galvanized)	230.000	LB
518-01001	Bridge Expansion Joint (Asphaltic Plug)	160.000	LF
518-01004	Bridge Expansion Device (0-4 Inch)	59.000	LF
606-00301	Guardrail Type 3 (6-3 Post Spacing)	3,075.000	LF
606-00350	Guardrail Type 3 (Double) (6-3 Post Spacing)	1,325.000	LF
606-01370	Transition Type 3G	7.000	EACH
606-01460	Median Terminal	4.000	EACH
606-02005	End Anchorage (Flared)	8.000	EACH
609-21011	Curb and Gutter Type 2 (Section I-M)	1,115.000	LF
610-00020	Median Cover Material (Patterned Concrete)	4,250.000	SF
610-00030	Median Cover Material (Concrete)	2,430.000	SF
613-00206	2 Inch Electrical Conduit (Bored)	1,325.000	LF
613-00306	3 Inch Electrical Conduit (Bored)	1,670.000	LF
614-70337	Traffic Signal Face (12-12-12) (Install Only)	16.000	EACH
614-81135	Traffic Signal-Light Pole Steel (1-35 Foot Mast Arm)	1.000	EACH
614-81140	Traffic Signal-Light Pole Steel (1-40 Foot Mast Arm)	1.000	EACH
614-81160	Traffic Signal Light Pole Steel (1-60 Foot Mast Arm)	2.000	EACH
614-81170	Traffic Signal-Light Pole Steel (1-70 Foot Mast Arm)	1.000	EACH
614-81175	Traffic Signal-Light Pole Steel (1-75 Foot Mast Arm)	2.000	EACH
620-00002	Field Office (Class 2)	1.000	EACH
620-00012	Field Laboratory (Class 2)	1.000	EACH
625-00000	Construction Surveying	1.000	L S
626-00000	Mobilization	1.000	L S
627-00009	Modified Epoxy Pavement Marking(Inlaid)	488.000	GAL
627-00011	Pavement Marking Paint (Waterborne)	1,464.000	GAL
627-30405	Preformed Thermoplastic Pavement Marking (Word-Symbol)	1,406.000	SF
627-30410	Preformed Thermoplastic Pavement Marking (Xwalk-Stop Line)	27,425.000	SF
630-00000	Flagging	1,600.000	HOUR
630-00007	Traffic Control Inspection	140.000	DAY

<b>Item No.</b>	<b>Description</b>	<b>Quantity</b>	<b>Units</b>
	Major Items		
630-00012	Traffic Control Management	80.000	DAY
630-80002	Flashing Beacon (Solar)	40.000	EACH
630-80370	Concrete Barrier (Temporary)	2,000.000	LF
630-85010	Impact Attenuator (Temporary)	4.000	EACH
630-85040	Impact Attenuator (Truck Mounted Attenuator) (Temporary)	2.000	EACH
630-86800	Traffic Signal (Temporary)	1.000	L S