

COLORADO PROJECT

STA0243-087


As Constructed

No Revisions:

Revised:

Void:

INDEX			CONTRACT ITEM NUMBER	CONTRACT ITEM	PROJECT TOTALS		
B O O K	P A G E	S H E E T			UNIT	PLAN QUANTITY	AS CONST.
			202-00002	Removal of Structure (Special)	EACH	1	
			202-00090	Removal of Delineator	EACH	168	
			202-00200	Removal of Sidewalk	SY	6	
			202-00220	Removal of Asphalt Mat	SY	5,163	
			202-00240	Removal of Asphalt Mat (Planing)	SY	11,374	
			203-00050	Unsuitable Material	CY	500	
			203-00060	Embankment Material (Complete In Place)	CY	2,992	
			208-00035	Aggregate Bag	LF	500	
			208-00103	Removal and Disposal of Sediment (Labor)	HOUR	10	
			208-00105	Removal and Disposal of Sediment (Equipment)	HOUR	4	
			208-00106	Sweeping (Sediment Removal)	HOUR	144	
			208-00107	Removal of Trash	HOUR	40	
			210-04010	Adjust Manhole	EACH	8	
			212-00006	Seeding (Native)	ACRE	0.15	
			212-00032	Soil Conditioning	ACRE	0.15	
			216-00101	Soil Retention Blanket (Straw-Coconut)			
				(Photodegradable Class 1)	SY	730	
			304-06007	Aggregate Base Course (Class 6)	CY	1,808	
			403-00720	Hot Mix Asphalt (Patching) (Asphalt)	TON	500	
			403-34741	Hot Mix Asphalt (Grading SX) (75) (PG 64-22)	TON	23,652	
			403-34751	Hot Mix Asphalt (Grading SX) (75) (PG 64-28)	TON	21,268	
			411-10255	Emulsified Asphalt (Slow-Setting)	GAL	23,662	
			601-01000	Concrete Class B	CY	0.3	
			603-10120	12 Inch Corrugated Steel Pipe	LF	10	
			607-11525	Fence (Plastic)	LF	100	
			608-00010	Concrete Curb Ramp	SY	16	
			608-00015	Detectable Warnings	SF	42	

Computer File Information		SUMMARY OF APPROXIMATE QUANTITIES		Project No./Code	
Creation Date: 07-Feb-2017	Initials:			STA0243-087	
Last Modification Date:	Initials:			20856	
Full Path: \\tsclient\C\Projects?56 - US 24-El Paso Elbert\...	Designer: J.D. Miller	Region: 4	Sheet Number: 11		
Drawing File Name: 20856_Sheet11	Detailer: J.D. Miller	Unit Leader: TAM			
AutoCAD by Autodesk					

COLORADO PROJECT

STA0243-087


As Constructed

No Revisions:

Revised:

Void:

INDEX			CONTRACT ITEM NUMBER	CONTRACT ITEM	PROJECT TOTALS		
B O O K	P A G E	S H E E T			UNIT	PLAN QUANTITY	AS CONST.
			612-00003	Delineator (Type III)	EACH	46	
			612-00101	Delineator (Drivable Concrete Installation) (Type			
				I)	EACH	122	
			620-00001	Field Office (Class 1)	EACH	1	
			620-00012	Field Laboratory (Class 2)	EACH	1	
			620-00020	Sanitary Facility	EACH	2	
			625-00000	Construction Surveying	L S	1	
			626-00000	Mobilization	L S	1	
			626-01104	Public Information Services (Tier IV)	L S	1	
			627-00008	Modified Epoxy Pavement Marking	GAL	395	
			627-00013	Pavement Marking Paint (High Build)	GAL	1,186	
			627-30405	Preformed Thermoplastic Pavement Marking			
				(Word-Symbol)	SF	130	
			627-30410	Preformed Thermoplastic Pavement Marking			
				(Xwalk-Stop Line)	SF	786	
			630-00000	Flagging	HOUR	2,025	
			630-00007	Traffic Control Inspection	DAY	30	
			630-00012	Traffic Control Management	DAY	60	
			630-80001	Flashing Beacon (Portable)	EACH	2	
			630-80338	Barricade (Type 3 M-D) (Temporary)	EACH	8	
			630-80341	Construction Traffic Sign (Panel Size A)	EACH	53	
			630-80342	Construction Traffic Sign (Panel Size B)	EACH	74	
			630-80343	Construction Traffic Sign (Panel Size C)	EACH	8	
			630-80344	Construction Traffic Sign (Special)	SF	168	
			630-80350	Vertical Panel	EACH	50	
			630-80355	Portable Message Sign Panel	EACH	2	
			630-80360	Drum Channelizing Device	EACH	100	

Computer File Information		SUMMARY OF APPROXIMATE QUANTITIES		Project No./Code	
Creation Date: 07-Feb-2017	Initials:			STA0243-087	
Last Modification Date:	Initials:			20856	
Full Path: \\tsclient\C\Projects\56 - US 24-El Paso Elbert\...	Designer: J.D. Miller	Region: 4	Sheet Number: 12		
Drawing File Name: 20856_Sheet12	Detailer: J.D. Miller	Unit Leader: TAM			
AutoCAD by Autodesk					

