

Proposal Schedule of Items

Contract ID: C21254

Project(s): STA067A-039

Contractor: _____

SECTION: 0001 BID ITEMS

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0005	202-00090 Removal of Delineator	1,126.000 EACH	_____	_____	_____	_____
0010	202-00206 Removal of Concrete Curb Ramp	1.800 SY	_____	_____	_____	_____
0015	202-00226 Removal of Asphalt Mat (Special)	35.000 SY	_____	_____	_____	_____
0020	202-00240 Removal of Asphalt Mat (Planing)	9,174.000 SY	_____	_____	_____	_____
0025	202-00425 Removal of Bridge Railing	216.000 LF	_____	_____	_____	_____
0030	202-00810 Removal of Ground Sign	97.000 EACH	_____	_____	_____	_____
0035	202-00821 Removal of Sign Panel	27.000 EACH	_____	_____	_____	_____
0040	202-01130 Removal of Guardrail Type 3	9,931.000 LF	_____	_____	_____	_____
0045	202-01300 Removal of End Anchorage	34.000 EACH	_____	_____	_____	_____
0050	203-00010 Unclassified Excavation (Complete In Place)	400.000 CY	_____	_____	_____	_____
0055	203-00060 Embankment Material (Complete In Place)	585.000 CY	_____	_____	_____	_____
0060	203-01597 Potholing	40.000 HOUR	_____	_____	_____	_____
0065	208-00002 Erosion Log Type 1 (12 Inch)	2,000.000 LF	_____	_____	_____	_____

Proposal Schedule of Items

Contract ID: C21254

Project(s): STA067A-039

Contractor: _____

SECTION: 0001 BID ITEMS

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0070	208-00035 Aggregate Bag	30.000 LF	_____	_____	_____	_____
0075	208-00045 Concrete Washout Structure	1.000 EACH	_____	_____	_____	_____
0080	208-00103 Removal and Disposal of Sediment (Labor)	20.000 HOUR	_____	_____	_____	_____
0085	208-00105 Removal and Disposal of Sediment (Equipment)	20.000 HOUR	_____	_____	_____	_____
0090	208-00106 Sweeping (Sediment Removal)	100.000 HOUR	_____	_____	_____	_____
0095	210-04035 Modify Guardrail (Special)	11,977.000 LF	_____	_____	_____	_____
0100	211-00100 Drilling Hole	240.000 LF	_____	_____	_____	_____
0105	211-02275 Cement Grout	20.000 CY	_____	_____	_____	_____
0110	240-00000 Wildlife Biologist	5.000 HOUR	_____	_____	_____	_____
0115	240-00010 Removal of Nests	10.000 HOUR	_____	_____	_____	_____
0120	304-06000 Aggregate Base Course (Class 6)	600.000 TON	_____	_____	_____	_____
0125	304-08000 Aggregate Base Course (Shoulder Material)	3,851.000 TON	_____	_____	_____	_____
0130	307-00000 Hydrated Lime	1,118.000 TON	_____	_____	_____	_____

Proposal Schedule of Items

Contract ID: C21254

Project(s): STA067A-039

Contractor: _____

SECTION: 0001 BID ITEMS

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0135	403-00720 Hot Mix Asphalt (Patching) (Asphalt)	105.000 TON	_____	_____	_____	_____
0140	403-36721 Hot Mix Asphalt (Grading ST)(75)(PG 58-28)	49,755.000 TON	_____	_____	_____	_____
0145	406-09500 Cold Bituminous Pavement (Recycle)	338,682.000 SY	_____	_____	_____	_____
0150	411-10255 Emulsified Asphalt (Slow-Setting)	45,634.000 GAL	_____	_____	_____	_____
0155	411-90040 Recycling Agent	626,806.000 GAL	_____	_____	_____	_____
0160	518-03000 Sawing and Sealing Bridge Joint	241.000 LF	_____	_____	_____	_____
0165	606-00301 Guardrail Type 3 (6-3 Post Spacing) (31" MGS)	13,187.000 LF	_____	_____	_____	_____
0170	606-01370 Transition Type 3G (31" MGS)	12.000 EACH	_____	_____	_____	_____
0175	606-01385 Transition Type 3J (31" MGS)	1.000 EACH	_____	_____	_____	_____
0180	606-01390 End Anchorage Type 3K (31" MGS)	1.000 EACH	_____	_____	_____	_____
0185	606-02003 End Anchorage (Nonflared) (31" MGS)	18.000 EACH	_____	_____	_____	_____
0190	606-02005 End Anchorage (Flared) (31" MGS)	26.000 EACH	_____	_____	_____	_____
0195	606-11010 Bridge Rail Type 10R	216.000 LF	_____	_____	_____	_____

Proposal Schedule of Items

Contract ID: C21254

Project(s): STA067A-039

Contractor: _____

SECTION: 0001 BID ITEMS

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0200	608-00015 Detectable Warnings	176.000 SF	_____	_____	_____	_____
0205	612-00036 Delineator (Flexible) (Square Base)	1,126.000 EACH	_____	_____	_____	_____
0210	614-00011 Sign Panel (Class I)	447.000 SF	_____	_____	_____	_____
0215	614-00012 Sign Panel (Class II)	838.000 SF	_____	_____	_____	_____
0220	614-00013 Sign Panel (Class III)	66.000 SF	_____	_____	_____	_____
0225	614-01503 Steel Sign Support (2-Inch Round)(Post and Socket)	48.000 EACH	_____	_____	_____	_____
0230	614-01573 Steel Sign Support (2-1/2 Inch Round NP-40)(Post & Slipbase)	64.000 EACH	_____	_____	_____	_____
0235	614-80001 Flashing Beacon (Solar Powered)	3.000 EACH	_____	_____	_____	_____
0240	614-80385 Rumble Strip	135,084.000 LF	_____	_____	_____	_____
0245	620-00002 Field Office (Class 2)	1.000 EACH	_____	_____	_____	_____
0250	620-00012 Field Laboratory (Class 2)	1.000 EACH	_____	_____	_____	_____
0255	620-00020 Sanitary Facility	1.000 EACH	_____	_____	_____	_____
0260	625-00000 Construction Surveying	1.000 L S	_____	_____	_____	_____

Proposal Schedule of Items

Contract ID: C21254

Project(s): STA067A-039

Contractor: _____

SECTION: 0001 BID ITEMS

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0265	626-00000 Mobilization	1.000 L S	_____	_____	_____	_____
0270	627-00009 Modified Epoxy Pavement Marking(Inlaid)	2,494.000 GAL	_____	_____	_____	_____
0275	627-00011 Pavement Marking Paint (Waterborne)	5,340.000 GAL	_____	_____	_____	_____
0280	627-30405 Preformed Thermoplastic Pavement Marking (Word-Symbol)	655.000 SF	_____	_____	_____	_____
0285	627-30410 Preformed Thermoplastic Pavement Marking (Xwalk-Stop Line)	426.000 SF	_____	_____	_____	_____
0290	630-00000 Flagging	3,636.000 HOUR	_____	_____	_____	_____
0295	630-00001 Pilot Car Operation	800.000 HOUR	_____	_____	_____	_____
0300	630-00007 Traffic Control Inspection	78.000 DAY	_____	_____	_____	_____
0305	630-00012 Traffic Control Management	101.000 DAY	_____	_____	_____	_____
0310	630-80001 Flashing Beacon (Portable)	2.000 EACH	_____	_____	_____	_____
0315	630-80341 Construction Traffic Sign (Panel Size A)	38.000 EACH	_____	_____	_____	_____
0320	630-80342 Construction Traffic Sign (Panel Size B)	75.000 EACH	_____	_____	_____	_____
0325	630-80343 Construction Traffic Sign (Panel Size C)	24.000 EACH	_____	_____	_____	_____

Proposal Schedule of Items

Contract ID: C21254

Project(s): STA067A-039

Contractor: _____

SECTION: 0001 BID ITEMS

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0330	630-80344 Construction Traffic Sign (Special)	192.000 SF	_____	_____	_____	_____
0335	630-80355 Portable Message Sign Panel	6.000 EACH	_____	_____	_____	_____
0340	630-80360 Drum Channelizing Device	100.000 EACH	_____	_____	_____	_____
0345	630-80363 Drum Channelizing Device (With Light) (Flashing)	10.000 EACH	_____	_____	_____	_____
0350	630-80364 Drum Channelizing Device (With Light) (Steady Burn)	20.000 EACH	_____	_____	_____	_____
0355	630-80380 Traffic Cone	200.000 EACH	_____	_____	_____	_____
0360	630-80510 Mobile Pavement Marking Zone	1.000 L S	_____	_____	_____	_____
0365	630-85011 Impact Attenuator (Temporary)	100.000 DAY	_____	_____	_____	_____
0370	700-70023 F/A On-The-Job Trainee	1,920.000 F A	_____	_____	_____	_____

Section: 0001

Total: _____

Total Bid: _____

I hereby certify that I have the authority to submit this bid

Signature

Agency

Date
