

TABULATION OF STRIPING (1 OF 3)

SH 9									
APPROX STATION	TO APPROX STATION	DIRECTION	APPROX LENGTH OF EXISTING					627-00009	
			YELLOW			WHITE		MODIFIED EPOXY PAVEMENT MARKING (INLAID)	
			4" SOLID DOUBLE (1 GAL/120 LF) CENTER	4" SKIP (1 GAL/960 LF) CENTER	4" SOLID /SKIP (1 GAL/192 LF) CENTER	4" SOLID (1 GAL/240 LF) EDGE	8" SOLID (1 GAL/120 LF) CHANNELIZING		
			LF			LF		YELLOW	WHITE
					GAL				
00+10	0+40	NB	30			65	125	0.3	1.3
00+40	15+50	NB	1510			1510		12.6	6.3
15+95	23+20	NB	725			725		6.0	3.0
23+20	37+50	NB			1430	1430		7.5	6.0
37+50	38+05	NB				55			0.2
38+05	45+80	NB			775	775		4.0	3.2
45+80	59+50	NB	1370			1370		11.4	5.7
59+50	60+25	NB				75			0.3
60+25	106+50	NB	4625			4625		38.5	19.3
106+50	117+50	NB			1100	1100		5.7	4.6
117+50	162+00	NB		4450		4450		4.6	18.5
162+00	173+00	NB			1100	1100		5.7	4.6
173+00	192+70	NB	1970			1970		16.4	8.2
192+70	193+40	NB				70			0.3
193+40	209+60	NB	1620			1620		13.5	6.8
209+60	218+35	NB			875	875		4.6	3.7
218+35	229+80	NB		1145		1145		1.2	4.8
229+80	248+00	NB			1820	1820		9.5	7.6
248+00	253+85	NB		585		585		0.6	2.4
253+85	255+60	NB			175	175		0.9	0.7
255+60	256+20	NB				60			0.3
256+20	263+00	NB			680	680		3.5	2.8
263+00	285+50	NB	2250			2250		18.8	9.4
285+50	297+15	NB			1165	1165		6.1	4.9
297+15	331+50	NB		3435		3435		3.6	14.3
331+50	353+70	NB			2220	2220		11.6	9.3
353+70	366+40	NB		1270		1270		1.3	5.3
366+40	377+00	NB			1060	1060		5.5	4.4
377+00	383+35	NB	635			635		5.3	2.7
383+35	394+00	NB			1065	1065		5.6	4.4
SH 9 STRIPING SUBTOTAL (1 OF 3)								204.3	165.3

US 50									
APPROX STATION	TO APPROX STATION	DIRECTION	APPROX LENGTH OF EXISTING					627-00009	
			YELLOW			WHITE		MODIFIED EPOXY PAVEMENT MARKING (INLAID)	
			4" SOLID DOUBLE (1 GAL/ 120 LF) CENTER	4" SKIP (1 GAL/960 LF) CENTER	4" SOLID /SKIP (1 GAL/192 LF) CENTER	4" SOLID (1 GAL/240 LF) EDGE	4" SKIP (1 GAL/960 LF) LANE		
			LF			LF		YELLOW	WHITE
					GAL				
3780+00	3800+00	WB	2000			2000		16.7	8.3
3800+00	3809+10	WB	910			910	910	7.6	4.7
3809+10	3809+70	WB	60			60		0.5	0.1
3809+70	3816+75	WB	705			705	705	5.9	3.7
3816+75	3817+40	WB					65		0.1
3817+40	3822+20	WB	480			480	480	4.0	6.5
3822+20	3825+25	WB	305			305	305	2.5	2.0
3825+25	3837+70	WB	1245			1245	1245	10.4	6.5
3837+70	3846+30	WB			860	860	860	4.5	4.5
3846+30	3856+50	WB	1020			1020	1020	8.5	5.3
3856+50	3865+70	WB			920	920	920	4.8	4.8
3865+70	3881+10	WB	1540			1540	1540	12.8	8.0
3881+10	3887+50	WB	640			640		5.3	2.7
3887+50	3908+50	WB			2100	2100		10.9	8.8
3908+50	3937+00	WB	2850			2850		23.8	11.9
3937+00	3944+50	WB			750	750		3.9	3.1
3944+50	3948+40	WB		390		390		0.4	1.6
3948+40	3953+50	WB			510	510		2.7	2.1
3953+50	3974+70	WB	2120			2120		17.7	8.8
3974+70	3993+00	WB			1830	1830		9.5	7.6
3993+00	4029+00	WB	3600			3600		30.0	15.0
4029+00	4038+00	WB			900	900		4.7	3.8
4038+00	4040+00	WB	200					1.7	
4040+00	4061+00	WB	2100			2100		17.5	8.8
4061+00	4065+00	WB	400			400	400	3.3	2.2
4065+00	4073+20	WB	820			820	820	6.8	10.3
4073+60	4078+75	WB	515			515	515	4.3	6.4
4078+75	4080+30	WB	155			155	155	1.3	0.9
4080+30	4110+00	WB	2997			2997		25.0	12.5
4110+00	4111+00	WB				100			0.4
US 50 STRIPING SUBTOTAL (1 OF 3)								247.0	161.4

NOTES:

- 1) THE APPLICATION RATES SHOWN ABOVE IN UNITS OF GAL/LF ARE FOR ESTIMATING PURPOSES ONLY. THESE RATES INCLUDE THE LENGTH OF GAPS BETWEEN SKIPS OR DOTS. SEE THE PROJECT SPECIFICATIONS FOR ACTUAL APPLICATION RATE REQUIREMENTS.
- 2) THE CONTRACTOR SHALL CONTACT THE CDOT TRAFFIC UNIT AT LEAST TWO WEEKS PRIOR TO LAYING OUT FINAL CENTERLINE STRIPES.

Print Date: 1/24/2017
 File Name: 21255DES_Tab_Stripe01.dgn
 Horiz. Scale: 1:1 Vert. Scale: N/A
TRANSPORTATION
AECOM
 AECOM Technical Services, Inc.
 2315 Bridgeway Parkway, Suite 150 Colorado Springs, CO 80920
 T 719.531.0001 www.aecom.com

Sheet Revisions		
Date:	Comments	Init.

Colorado Department of Transportation

 1480 Quail Lake, Suite A
 Colorado Springs, CO 80906
 Phone: 719-634-2323 FAX: 719-227-3298
Region 2 DW

As Constructed	TABULATION OF STRIPING	
No Revisions:	Designer: JAB	Structure Numbers
Revised:	Detailer: LMB	Subset Sheets: 1 of 3
Void:	Subset: TAB-STRIPES	

Project No./Code
 STA 0503-089
 21255
 Sheet Number 26

jason.bonini:10:06:09 PM p:\617479-PWINT\acemonline\local\AECOM_DS01_NA\Documents\60505397-US50_Royal Gorge West_SH9 Jct North\900 Work\910 CAD\02 SHEETS\02_Roadway\21255DES_Tab_Stripe01.dgn

TABULATION OF STRIPING (2 OF 3)

SH 9										
APPROX STATION	TO APPROX STATION	DIRECTION	APPROX LENGTH OF EXISTING					627-00009		
			YELLOW			WHITE		MODIFIED EPOXY PAVEMENT MARKING (INLAID)		
			4" SOLID DOUBLE (1 GAL/120 LF) CENTER	4" SKIP (1 GAL/960 LF) CENTER	4" SOLID /SKIP (1 GAL/192 LF) CENTER	4" SOLID (1 GAL/240 LF) EDGE	8" SOLID (1 GAL/120 LF) CHANNELIZING			
			LF			LF		YELLOW	WHITE	
					GAL					
394+00	411+80	NB		1780		1780		1.9	7.4	
411+80	420+90	NB			910	910		4.7	3.8	
420+90	452+20	NB	3130			3130		26.1	13.0	
453+20	460+70	NB	750			750		6.3	3.1	
460+70	471+20	NB			1050	1050		5.5	4.4	
471+20	485+40	NB		1420		1420		1.5	5.9	
485+40	493+50	NB			810	810		4.2	3.4	
493+50	525+15	NB	3165			3165		26.4	13.2	
525+15	549+45	NB			2430	2430		12.7	10.1	
549+45	558+30	NB		885		885		0.9	3.7	
558+30	565+00	NB			670	670		3.5	2.8	
565+00	571+00	NB	600			600		5.0	2.5	
571+00	571+75	NB				75			0.3	
571+75	591+25	NB			1950	1950		10.2	8.1	
591+25	608+50	NB	1725			1725		14.4	7.2	
608+50	616+35	NB			785	785		4.1	3.3	
616+35	621+70	NB		535		535		0.6	2.2	
621+70	631+30	NB			960	960		5.0	4.0	
631+30	636+80	NB	550			550		4.6	2.3	
636+80	645+70	NB			890	890		4.6	3.7	
645+70	656+90	NB		1120		1120		1.2	4.7	
656+90	664+00	NB			710	710		3.7	3.0	
664+00	675+50	NB	1150			1150		9.6	4.8	
675+50	685+20	NB			970	970		5.1	4.0	
685+20	696+00	NB		1080		1080		1.1	4.5	
696+00	707+00	NB			1100	1100		5.7	4.6	
707+00	727+60	NB	2060			2060		17.2	8.6	
727+60	736+50	NB			890	890		4.6	3.7	
736+50	760+00	NB		2350		2350		2.5	9.8	
760+00	765+80	NB			580	580		3.0	2.4	
SH 9 STRIPING SUBTOTAL (2 OF 3)							195.9	154.5		

US 50										
APPROX STATION	TO APPROX STATION	DIRECTION	APPROX LENGTH OF EXISTING					627-00009		
			YELLOW			WHITE		MODIFIED EPOXY PAVEMENT MARKING (INLAID)		
			4" SOLID DOUBLE (1 GAL/ 120 LF) CENTER	4" SKIP (1 GAL/960 LF) CENTER	4" SOLID /SKIP (1 GAL/192 LF) CENTER	4" SOLID (1 GAL/240 LF) EDGE	4" SKIP (1 GAL/960 LF) LANE			4" BROKEN (1 GAL/360 LF) DOTTED
			LF			LF		YELLOW	WHITE	
					GAL					
4111+00	4152+50	WB			4150	4150		21.6	17.3	
4152+50	4201+80	WB	4930			4930		41.1	20.5	
4201+80	4202+60	WB	80			80		0.7	1.0	
4203+00	4203+70	WB	70					0.6	0.6	
4203+70	4207+25	WB	355			355		3.0	4.4	
4207+25	4207+90	WB	65					0.5	0.5	
4207+90	4208+55	WB	65			65		0.5	0.8	
4208+55	4208+90	WB	35					0.3	0.3	
4208+90	4209+30	WB	40				40	0.3	0.1	
4209+30	4211+60	WB	230			230		1.9	1.3	
4211+60	4212+30	WB	70					0.6		
4212+30	4219+20	WB			690	690		3.6	2.9	
4219+20	4238+60	WB		1940		1940		2.0	8.1	
4238+60	4250+00	WB			1140	1140		5.9	4.8	
4250+00	4260+35	WB	1035			1035		8.6	4.3	
3780+00	3804+00	EB				2400			10.0	
3804+00	3809+90	EB	590			590		4.9	2.5	
3809+90	3811+15	EB	125			125		1.0	0.7	
3811+15	3816+75	EB	560			560		4.7	7.0	
3816+75	3817+55	EB				80			0.3	
3817+55	3822+00	EB	445			445		3.7	1.9	
3822+00	4059+00	EB				23700			98.8	
4059+00	4065+00	EB	600			600		5.0	2.5	
4065+00	4068+20	EB	320			320		2.7	1.8	
4068+20	4073+25	EB				505			6.3	
4073+25	4080+00	EB	675			675		5.6	2.8	
4080+00	4110+10	EB				3010			12.5	
4111+10	4183+91	EB				7281	7281		37.9	
4183+91	4190+55	EB				664			2.8	
4190+55	4199+85	EB	930			930		7.8	3.9	
US 50 STRIPING SUBTOTAL (2 OF 3)							126.6	258.6		

NOTES:

- THE APPLICATION RATES SHOWN ABOVE IN UNITS OF GAL/LF ARE FOR ESTIMATING PURPOSES ONLY. THESE RATES INCLUDE THE LENGTH OF GAPS BETWEEN SKIPS OR DOTS. SEE THE PROJECT SPECIFICATIONS FOR ACTUAL APPLICATION RATE REQUIREMENTS.
- THE CONTRACTOR SHALL CONTACT THE CDOT TRAFFIC UNIT AT LEAST TWO WEEKS PRIOR TO LAYING OUT FINAL CENTERLINE STRIPES.

Print Date: 1/24/2017		Sheet Revisions				Colorado Department of Transportation 1480 Quail Lake, Suite A Colorado Springs, CO 80906 Phone: 719-634-2323 FAX: 719-227-3298 Region 2 DW	As Constructed No Revisions: Revised: Void:	TABULATION OF STRIPING			Project No./Code STA 0503-089	
File Name: 21255DES_Tab_Stripe02.dgn		Date:	Comments	Init.							Designer: JAB Detailer: LMB Subset: TAB-STRIPE	Structure Numbers Subset Sheets: 2 of 3
Horiz. Scale: 1:1 Vert. Scale: N/A												

jason.bonini:10:06:20 PM p:\617479-PWINT.aecomonline.local\AECOM_DS01_NA\Documents\60505397-US50_Royal Gorge West_SH9 Jct North\900 Work\910 CAD\02 SHEETS\02_Roadway\21255DES_Tab_Stripe02.dgn

TABULATION OF STRIPING (3 OF 3)

SH 9									
APPROX STATION	TO APPROX STATION	DIRECTION	APPROX LENGTH OF EXISTING					627-00009	
			YELLOW			WHITE		MODIFIED EPOXY PAVEMENT MARKING (INLAID)	
			4" SOLID DOUBLE (1 GAL/120 LF) CENTER	4" SKIP (1 GAL/960 LF) CENTER	4" SOLID /SKIP (1 GAL/192 LF) CENTER	4" SOLID (1 GAL/240 LF) EDGE	8" SOLID (1 GAL/120 LF) CHANNELIZING		
			LF			LF		YELLOW	WHITE
765+80	852+90	NB	8710			8710		72.6	36.3
852+90	853+45	NB				55			0.2
853+45	860+40	NB			695	695		3.6	2.9
860+40	868+00	NB		760		760		0.8	3.2
868+00	877+00	NB			900	900		4.7	3.8
877+00	886+00	NB	900			900		7.5	3.8
886+00	903+00	NB			1700	1700		8.9	7.1
903+00	908+50	NB	550			550		4.6	2.3
908+50	917+50	NB			900	900		4.7	3.8
917+50	918+50	NB		100				0.1	
918+50	945+40	NB		2690		2690		2.8	11.2
945+40	952+00	NB			660	660		3.4	2.8
00+15	0+55	SB				60	130		1.3
00+55	37+50	SB				3695			15.4
38+00	59+50	SB				2150			9.0
60+10	120+00	SB				5990			25.0
120+60	192+50	SB				7190			30.0
193+45	255+50	SB				6205			25.9
256+20	570+50	SB				31430			131.0
571+90	853+00	SB				28110			117.1
853+60	952+00	SB				9840			41.0
SH 9 STRIPING SUBTOTAL (3 OF 3)								113.7	473.1

US 50									
APPROX STATION	TO APPROX STATION	DIRECTION	APPROX LENGTH OF EXISTING					627-00009	
			YELLOW			WHITE		MODIFIED EPOXY PAVEMENT MARKING (INLAID)	
			4" SOLID DOUBLE (1 GAL/ 120 LF) CENTER	4" SKIP (1 GAL/960 LF) CENTER	4" SOLID /SKIP (1 GAL/192 LF) CENTER	4" SOLID (1 GAL/240 LF) EDGE	4" SKIP (1 GAL/960 LF) LANE		
			LF			LF		YELLOW	WHITE
4199+85	4206+60	EB				675			8.4
4206+60	4206+85	EB				25			0.1
4207+20	4208+40	EB				120			0.5
4209+00	4211+70	EB				270			1.1
4212+35	4217+00	EB				465			1.9
4217+60	4260+35	EB				4275			17.8
US 50 STRIPING SUBTOTAL (3 OF 3)								0.0	29.8

627-00009		
MODIFIED EPOXY PAVEMENT MARKING (INLAID)		
YELLOW	WHITE	GAL
SH 9 SUBTOTAL (1 OF 3)	204.3	165.3
US 50 SUBTOTAL (1 OF 3)	247.0	161.4
SH 9 SUBTOTAL (2 OF 3)	195.9	154.5
US 50 SUBTOTAL (2 OF 3)	126.6	258.6
SH 9 SUBTOTAL (3 OF 3)	113.7	473.1
US 50 SUBTOTAL (3 OF 3)	0.0	29.8
SH 9 STRIPING SUBTOTAL	1306.8	
US 50 STRIPING SUBTOTAL	823.4	
PROJECT TOTAL	2131	

US50/SH9								
LOCATION	APPROX STATION	DIRECTION	SYMBOL				627-30405	627-30410
			TURN ARROW (15.5 SF)	MERGE ARROW (58 SF)	STOP BAR (24")	YIELD BAR (12") (MUTCD FIG 3B-16)	PREFORMED THERMOPLASTIC PAVEMENT MARKING (WORD-SYMBOL)	PREFORMED THERMOPLASTIC PAVEMENT MARKING (XWALK-STOP LINE)
			EA	EA	LF	LF	SF	SF
SH 9	0+20	LT			13		26	
SH 9	0+20	LT				14	21	
US 50	3800+13	LT		1		58		
US 50	3804+35	LT		1		58		
US 50	3812+80	RT	1			15.5		
US 50	3816+30	RT	1			15.5		
US 50	3817+90	LT	1			15.5		
US 50	3821+70	LT	1			15.5		
US 50	4068+20	RT	1			15.5		
US 50	4072+90	RT	1			15.5		
US 50	4073+90	LT	1			15.5		
US 50	4078+60	LT	1			15.5		
US 50	4183+91	RT		1		58		
US 50	4190+77	RT		1		58		
US 50	4200+05	RT	1			15.5		
US 50	4202+50	RT	1			15.5		
US 50	4204+00	LT	1			15.5		
US 50	4207+00	LT	1			15.5		
SH 9 SUBTOTAL							47	
US 50 SUBTOTAL						418		
PROJECT TOTAL						418	47	

NOTES:

- 1) THE APPLICATION RATES SHOWN ABOVE IN UNITS OF GAL/LF ARE FOR ESTIMATING PURPOSES ONLY. THESE RATES INCLUDE THE LENGTH OF GAPS BETWEEN SKIPS OR DOTS. SEE THE PROJECT SPECIFICATIONS FOR ACTUAL APPLICATION RATE REQUIREMENTS.
- 2) THE CONTRACTOR SHALL CONTACT THE CDOT TRAFFIC UNIT AT LEAST TWO WEEKS PRIOR TO LAYING OUT FINAL CENTERLINE STRIPES.

Print Date: 1/24/2017
 File Name: 21255DES_Tab_Stripe03.dgn
 Horiz. Scale: 1:1 Vert. Scale: N/A

TRANSPORTATION
AECOM
 AECOM Technical Services, Inc.
 2315 Bluffgate Parkway, Suite 150 Colorado Springs, CO 80920
 T 719.531.0001 www.aecom.com

Sheet Revisions		
Date:	Comments	Init.

Colorado Department of Transportation

1480 Quail Lake, Suite A
 Colorado Springs, CO 80906
 Phone: 719-634-2323 FAX: 719-227-3298

Region 2 **DW**

As Constructed

No Revisions:

Revised:

Void:

TABULATION OF STRIPING

Designer: JAB Structure Numbers
 Detailer: LMB
 Subset: TAB-STRIPES Subset Sheets: 3 of 3

Project No./Code

STA 0503-089

21255

Sheet Number **28**

p:\617479-PWINT.aecomonline\local\AECOM_DS01_NA\Documents\60505397-US50_Royal Gorge West_SH9_Jct North\900_CAD\02_SHEETS\02_Roadway\21255DES_Tab_Stripe03.dgn